

ADB Loan No.: 2834-IND		North Eastern Region Capital Cities Development & Investment Programme (NERCCDIP) Pre Bid Meeting: Invitation for Bid No: SIPMIU/MEG/14/2015/1 dated 27th November 2015	Meeting Date: 07.01.2016 at 14:00 hrs
Name of Package: Construction of Civil Works and Supply, Installation, Testing, Commissioning and Trial Run of Mechanical Equipment of 170 TPD Compost Plant at Shillong			
Contract Package: NERCCDIP/TR- 02/SHG/SWM /08			
RECORD OF PRE-BID QUERIES & CLARIFICATIONS			
Sr.No	Ref. RfP Section	Query	Clarification
1	Section 7.2, GCC, Clause 13.5 Pg.43	13.5 (b) Plant, Materials or services to be purchase by the contractor, from a nominated subcontractor (as defined in clause 5[Normiated subcontractors] or otherwise ; and for which there shall be included in the contract price; (i) the actual amounts paid (or due to be paid) by the contractor, and (ii) a sum for overhead charges and profit, calculated as a percentage of these actual amounts by applying the relevant rate(if any) stated in the appropriate Schedule. If there is no such rate, the percentage rate stated in the contract Data shall be applied. Query: Please clarify how much percentage rate will be applied for overhead charges and profit on the actual amount of provisional item/work?	Please refer to corrigendum No.1 issued.
2	Section 4, BOQ , Pg.4-43, Compost screening machinery	We understand that client would like to set up a compost Plant having 170 TPD capacity. However , in BOQ the client has specified capacity of each section as under: 1) Presorting section-15 TPH x 8 working hrs=120 TPD 2) Preparatory section- 7.5 TPH 3) Refinement section-3.75 TPH Queries 1) Please specify how much operation hours client has proposed for operation of the plant in order to justify the capacity of each section. 2) Considering 8 hrs of operation and amount of waste to be processed as 170 TPD in 8 hrs , we understand that capacities of each section should be as follows:- Presorting section - 22 TPH 2) Preparatory section - 11 TPH 3) Refinement section - 5.5 TPH 3) Please clarify capacity of proposed compost plant considering 8 hrs of operational hours.	Due to constraint of the space (area) availability, the capacity of the screening machinery is limited to 15 TPH, 7.5 TPH and 3.75 TPH for presorting, preparatory and finishing sections respectively. For the first five years, the screening machieries would work to a maximum of 9 hours per day as the maximum average waste inflow will be 135 TPD. Henceforth, similarly with increase in waste inflow, the working hours would be maximum of 10 hours till the 7th year (150 TPD) and maximum of 11 hours till the end of 10th year (165 TPD) and beyond to process design capacity of 170 TPD. Hence Bid conditions prevail.
3	Section II, Bid Data Sheet(BDS) , ITB 22.1	Please extend the bid submission deadline by 20 days from 29.01.2015 in order to get sufficient time to submit competitive and comprehensive Bid Proposal.	Bid conditions prevail.
4	Section 4, BOQ	Queries 1) Do we need to mention taxes and duties separately in BoQ provided in section 4? PI confirm or Do we quote item rate with taxes and duties ? If we quote item rates including taxes then we cannot mention taxes and duties separately. Please confirm. 2) we understand that client will pay us for quoted amount including all taxes and duties. PI confirm.	Yes, taxes and duties should be quoted seperately as specified in the BOQ Yes Taxes and duties will be paid as applicable.


 Project Director

