

**GOVERNMENT OF MEGHALAYA
OFFICE OF THE PROJECT DIRECTOR
STATE INVESTMENT PROJECT MANAGEMENT AND IMPLEMENTATION UNIT
ASIAN DEVELOPMENT BANK- ASSISTED NERCCDIP-PROJECT
URBAN AFFAIRS COMPLEX, DHANKHETI, SHILLONG.
E-mail pd.sipmiushillong@gmail.com, Phone No.0364-2505463**

No. SIPMIU/MEG/1/2015/34

Dated Shillong, the 25th May, 2015

Corrigendum No. 1

To the bid for

**Procurement of Construction of Additional Landfill Area of 8500 sqm, and Ancillary
Works (Phase 2) at Marten, Shillong**

Package No. NERCCDIP/TR- 02/SHG/PH2/ SWM /04

(Invitation for Bids No: SIPMIU / MEG/ 1/2015/1)

VOLUME I


1.1 Section IV – Bidding Forms

Page No 4-54, 8.0 BOQ for Road Lighting at Landfill Site under Tranche-II
(Phase-II)

Replace the 'BOQ for Road Lighting at Landfill Site under Tranche-II (Phase-II)' by
following BOQ


Project Director,
SIPMIU, Shillong.

8.0 BOQ for Road Lighting at Landfill Site under Tranche-II (Phase-II)							
Sl. No	Description of work	Unit	Quantity	Rate in Figure and words in bracket (Rs)	Total Amount (Rs)	Taxes and other Duties	Country of origin of selected Goods
1	Supply, delivery, fixing and commissioning of street light system comprising 9 m hot dip galvanized swaged pole conforming to IS:2713, IS:2629, 250 W HPSV lamp ,IP66 Aluminium die cast Luminary housing with toughened heat resistant glass with silicon gasket conforming to IS:10322 ,earthing, earth pit, all necessary accessories, fitting etc	Set	30				
2	Supplying, laying, Tying, Tagging, testing and commissioning of underground XLPE insulated round wire armoured 4C x 50 sq mm Aluminum cable laid including termination ,straight through joint, cost of digging of trenches, re-instatement, cable route marker etc.	Rmt	750.00				
	Cost of 3C x 2.5 sq mm PVC insulated copper cable for Pole height	Rmt	240.00				
3	Supplying and fixing load junction kit, Gland and 6A,6 kA MCB	Set	30				
4	Supplying, filling and fixing of 14 SWG weather proof with rubber gasket TP & N distributor board with two coats of epoxy and two coats of primer earthing arrangement, mechanical locking arrangement for MCB	Set	30				
5	Supplying, filling and fixing load junction kit MCB, brackets, Double pole etc.	Set	30				
	Total cost of Road lighting						


Project Director,
SIPMIU, Shillong.

1.2 Section 8 - Particular Conditions of contract, Part A Contract Data,
Clause no 13.8 page no 8-2

Replace the clause 13.8 by the clause below.

'The contract price shall be adjustable during contract execution only after 18 months of contract period.

Increase or decrease in the cost of labour and material shall be calculated quarterly.

The first statement of price adjustment shall be prepared in the quarter after 18 months in which the work was done from the date of start (i.e., after 18 months) to the end of quarter shall be taken into account. For subsequent statement, cost of work done during every quarter shall be taken into account. At the completion of work, the work done during the last quarter or fraction, thereof, shall be taken into account.

For the purpose of reckoning the work done during any period, the bills prepared during the period shall be considered. The dates of recording measurements in the Measurement Book by the Engineer's Representative shall be the guiding factor to decide the bills relevant to any period.'



Project Director,
SIPMIU, Shillong.