


Note

- 1. All dimensions are in mm & levels are in mt.
- 2. All bolt shall confirm to IS 1364-1967 of M-8.8 grade
- 3. All weld to be 6mm full fillet weld unless specified otherwise.
- 4. All welding shall confirm to IS 2062.
- Holes wherever required shall be made by drilling & gas cutting shall not be allowed
- 6. I.S. indicates indian standard.





2nd Floor, Bellevue Marskin Opposite Clinic Research Unit (Tribal) for Homoeopathy Malki -Dhankhed Shining -793001 Meghalaya,Indla +91 (0) 364 2505 446

Client


State Investment Program Management and Implementation Unit (SIPMIU) Government of Meghalaya

North Eastern Region Capital Cities
Development Investment Programme
for Shillong, Solid Waste Management
Section Showing Typical Arrangement
of Truss Between Grid L To M

Drawn	L.L		Eng check	P.A.J	
Dwg check	R.T.G			-	
Approved	S.K.S				
Scale at A2 Nts		Status DPR		Rev R0	

Drawing Number

MMD-260652-S-DR-SWM-00-1010



We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or ornission which is due to an error or ornission in data supplied to us by other

(1) - Pipe OD 127H (5.4mm Thk.) Rafter size 2 - Pipe OD 76.1 L (3.2mm Thk. (3) Tie Member Size - Pipe OD 127 H (5.4mm Thk. **(4**) - 2 x 101.6 OD (3.6mm Thk.) Purlin Size **(5)** Tie Beam - 2 ISMC-250 BOX (Double) - 2 ISMC-250 BOX (Double) Truss Column **(7**) Tie Beam - 2 ISMC-300 BOX (Double) **(8**) - 2 ISMC-300 BOX (Double) Truss Column

101.6L OD (3.6mm Thk.)

SCHEDULE OF MEMBER